

Creek Bend Boulevard Extension

Addendum 2

February 6, 2015

Contents: Additional questions received & responses

Creek Bend Boulevard Extension Addendum 2 Questions and Responses

Question 1: I spoke with the Park representative and was informed that bid items 149 Stormtrooper and 150 Control Manhole are not sold as separate items. Can the bid form be revised to reflect it as one bid item?

Response 1: The Stormtrooper and Control Manhole items will remain separate. It is up to the bidders to decide how to split the cost.

Question 2: Please provide bid item for irrigation sleeves.

Response 2: Irrigation sleeves are included on the Summary of Roadway Quantities (sheet 10) as 2", 4" and 6" conduit.

Question 3: Please reference sheets 83-85 Storm Trooper Stormwater Quality Interceptor... These drawings require "Bitumastic Exterior Coating" for the control manhole. Is this coating also required for the "Stormtrooper Aquifer Interceptor"?

Response 3: Bitumastic exterior coating is called out on the left side of the stormtrooper aquifer interceptors on Elevations ST-1, ST-2 and ST-3 as well as the right side of the control manhole on Plan Views ST-1/SB-1, ST-2/SB-2 and ST-3/SB-3.

Question 4: Please provide a typical section for the driveways.

Response 4: The pavement design for the asphalt driveway at station 12+77.71 shall conform to the City of Round Rock Transportation Criteria Manual pavement design for local residential streets.

Question 5: Paving typical section detail calls out for 7" of HMA CP with a 6" curb. The curb gutter needs to be 7" for this to work. Please clarify.

Response 5: A 7" concrete thickness for the gutter may be utilized to conform to the 7" thick HMA CP.

Question 6: Does the 24" gate valve on the 30" water line require a manhole (Sta. 1+13.84)? If it does, please provide a detail.

Response 6: A manhole is not required.

February 6, 2015

Question 7: How will removal of existing 12"/16"/24"/30" water lines be paid? See sheets 234, 236, 246, & 247.

Response 7: The removal of pipes and vaults will be paid for under item 510-22. This is listed as a per each item with a quantity of 1, but will include all of the demolition identified on sheet 235 unless otherwise specified.

Question 8: Do you have an estimated cost for this project?

Response 8: \$8,000,000

Question 9: Is work on the flow meter at Wyoming Springs included in this contract? Will we have to re-hook it up? If so, where? The pole is being removed. The same with the control panel. If this needs to be included what bid item should it go under?

Response 9: Please refer to notes 16, 17 and 18 on sheet 257.