



**ROUND ROCK TEXAS**  
UTILITIES & ENVIRONMENTAL SERVICES DEPARTMENT

**Mayor**  
Alan McGraw

**Mayor Pro-Tem**  
George White

**Councilmembers**  
Craig Morgan  
Joe Clifford  
Will Peckham  
John Moman  
Kris Whitfield

**City Manager**  
Laurie Hadley, Interim

**City Attorney**  
Stephan L. Sheets

## **Deep Wood Drive Box Culvert Repair**

### **Addendum No. 2**

The Top Anchor Straps shown in the sidewalk and detailed in the lower left-hand corner of sheet 2 of 2 of the Plans (Drawings) within Section 02000 of the Project Manual are to be fabricated from 2 ½ inch wide by ¼ inch thick ASTM A36 steel plates. These straps shall not be galvanized or oiled.

Note that as per Note 3 of the Specific Project Notes within Section 02000 of the Project Manual the aforementioned Top Anchor Straps are included in and subsidiary to the Bid Item for “Remove and Replace Reinforced Portland Cement Concrete Sidewalk”.