



NOTES:

1. REMOVE ENTIRE CONE SECTION AND DEMOLISH STRUCTURE TWO FEET (2') MINIMUM BELOW GROUND LEVEL.
2. IF LINE WHICH IS TO ABANDONED IN PLACE, EXTENDS UNDER EXISTING OR PROPOSED STRUCTURE, THEN THE ENTIRE LINE TO THE NEXT MANHOLE SHALL BE GROUTED OR SLURRY FILLED.
3. IF LINE IS NOT LOCATED UNDER A STRUCTURE, ABANDON EXISTING LINE IN PLACE BY PLUGGING BOTH ENDS OF LINE AND GROUTING AROUND PLUGS.
4. THE CONTRACTOR IS TO RECORD AND CERTIFY QUANTITIES OF GROUT OR SLURRY PUMPED. QUANTITIES MUST BE A MINIMUM OF 90% OF CALCULATED EXISTING VOID CAPACITY.

**RECORD SIGNED COPY
ON FILE AT U&ES DEPARTMENT**

APPROVED

03-01-18

DATE

THE ARCHITECT/ENGINEER ASSUMES
RESPONSIBILITY FOR THE APPROPRIATE
USE OF THIS DETAIL. (NOT TO SCALE)

CITY OF ROUND ROCK

DRAWING NO:
WW-15

**WASTEWATER MANHOLE
ABANDONMENT DETAIL**

